



माछापुच्छ्रे गाउँपालिका

Machhapuchchhre Rural Municipality



गाउँ कार्यपालिकाको कार्यालय

Office of the Rural Municipal Executive

पत्र संख्या

Letter No.:

चलानी नं.

Dispatch No.:



लाहाचोक, कास्की

Lahachowk, Kaski

गण्डकी प्रदेश, नेपाल

Gandaki Province, Nepal

मिति: २०८२/०२/२३

विषय: कोटेसन पेश सम्बन्धमा।

श्री आपूर्तिकर्ताहरु सबै,

प्रस्तुत विषयमा यस माछापुच्छ्रे गाउँपालिकामा आ. व २०८१।८२ को लागि यस माछापुच्छ्रे गाउँपालिकाको वार्षिक स्वीकृत कार्यक्रम अन्तर्गत वडा नं ६ को वडा कार्यालयको सभाहल निर्माण, वडा कार्यालय टनेल व्यवस्थापन शिर्षक योजनाको निर्माण कार्य गर्नुपर्ने भएकोले के कति दर रेटमा कार्य गर्न सकिन्छ सो को प्रति इकाई मुल्य सहित तपशिल अनुसारको Bill Of Quantity (BOQ) तथा कागजात संलग्न गरी यस कार्यालयमा सुचना प्रकाशन भएको मितिले सात दिन भित्र सिलबन्धी सहित उपलब्ध गराइदिनु हुन सम्बन्धित सबैमा यो सुचना प्रकाशन गरिएको छ।

तपशिल:

- १ दर रेट सहित प्रति इकाई मुल्य पेश गरेको ब्यहोराको निवेदन।
- २ कारोबार सञ्चालनका लागि अनुमति प्राप्त प्रमाण पत्र प्रतिलिपी।
- ३ Vat मा दर्ता भएको प्रमाण पत्र प्रतिलिपी।
- ४ २०८०।८१ को कर चुक्ता प्रमाण पत्रको प्रतिलिपी।
- ५ सुचिकृत नभएको भए सो को लागि निवेदन तथा आवश्यक कागजात।

बोधार्थ:

सुचना प्रविधि शाखा - वेब साइटमा अपलोड गरिदिनु हुन।

(भोजराज बगाले)

नि. प्रमुख प्रशासकीय अधिकृत



Machhapuchhre Rural Municipality
Office of the Rural Municipal Executive
Lahachok, Kaski



BILL OF QUANTITIES (BOQ)

योजनाको नाम :- वडा कार्यालयको सभाहल निर्माण, वडा कार्यालय टनेल
स्थान: वडा नं. ६ धिताल

आ.व: २०८१/८२

S.N.	Description of work	Quantity	Unit	Rate	Amount	Amount in word	Remarks
1	Information Board And Accessories	1.00	job	₹			
2	Dismantalling of Cement mortar masonry with deposition up to 10 mtr. Lead works	0.29	m ³				
3	Supplying and Installation of Aluminium Sliding Window Fitted with 5mm clear Glass without Net Section (88*38*1.1)	5.51	m ²				
4	Supplying and Installation of Aluminium Partition with 5mm thick Glass and 9mm thick Laminated board of Section (64*38*1.1)	8.55	m ²				
5	Procelain glazed flooring tile in (1:4) Cement Sand mortar	38.73	m ²				
6	12.5mm thick Cement plaster works on 1:6 cement mortar	55.44	m ²				
7	3 mm Flushing Plaster works on plaster punning works	55.44	m ²				
8	One coat apex ultimate (weather coat) paint excluding primer .	43.10	m ²	₹			
9	Concreting with ratio 1:3:6 (cement:sand:aggregate) of foundation, vertical faces and walls (cement concrete) including supply of materials and haulage	0.57	m ³				
10	Supplying and Installation of 10 gauge GI wire (50*50mm) fencing mesh	81.38	m ²				
11	Making ridge of 0.5mm C.G.I. coloured plain sheet and fitting with supply of materials all complete	1.88	m ²				
12	Supplying and fixing of 12" flower pot/ gamala-Plastic, round shaped 12"diameter*10"height(Bagmati orange)	18.00	Nos				
13	Supplying and fixing of MS black pipe truss with primer all complete	11.72	kg	₹			
14	Supplying and Installation of Insect net 40 mesh net " 120 GSM	87.19	m ²				
Sub Total							
VAT@13%							
Total with VAT							
Grand Total							

Grand Total in Words:

Name of Firm:

Address:

Contact No:

Signature:

Stamp